

Paper No. OTC-35247-MS | Enhancing FPSO Control Systems: A Dynamic Simulation and Virtual Commissioning Approach

José M. Nougués / Inprocess Technology & Consulting Group

Summary

- Introduction
- MPDS and OTS
- Virtual Commissioning
- Applications
- Conclusions



nprocess

Since 2006 helping the processing industries in solving design and operational issues



our **core business** is Process Simulation

keen to **share its knowledge** with clients




















Operator Training System (OTS)




ICSS and Multipurpose Dynamic Simulation OTS



ICSS and Multipurpose Dynamic Simulation OTS




Multipurpose Dynamic Model Integration with ICSS



Virtual Commissioning


- Signals Integration and Virtual Wiring
- Controllers Switchover
- Safety Logic Integration
- Perturbation Test
- Integrated Control Narrative Verification
- Commissioning Procedure Verification




Case: FPSO Gas Injection Start-up procedure verification



During the virtual commissioning of the topside process for an FPSO, the plant start-up procedure underwent thorough verification using dynamic simulation and DCS emulation.



OTC-35247-MS • Enhancing FPSO Control Systems: A Dynamic Simulation and Virtual Commissioning Approach • José M. Nougués



After the virtual commissioning and test of the compressor unit start-up the main conclusions are:

- With the current valve size (antisurge and throttle) and initial opening the GI 1st stage reaches the discharge trip condition when the system remain in full recycle after the motor start
- The GI 1st Stage reaches the PAHH (210 barg) at the discharge side if no override action on the throttle valve is enable after the motor start and the compressor Load
- The modification of the start-up procedure to avoid overpressurization is the following:
 - a) Pressurization and motor start are performed with throttle valve 10% (step 1)
 - b) Antistone wall controller is automatically enabled when the motor is started (step 9.1)
- With the suggested procedure where anti-stonewall is enabled, the compressor system does not pressurize
- It should be noted that 2nd stage discharge pressure stabilizes below the PALL (410 barg). Nevertheless, in the Control Narrative Review it was confirmed that the PALL setting could be decreased.

Real Plant Startup Experience: Pentanal vs. 2-Propylheptanol



Pentanal and 2-Propylheptanol Process


Pentanal Production Process

- Hydroformylation process
- Synthesis of Pentanal from butene or C4 mixtures
- Catalyst composition and selectivity towards Pentanal

2-Propylheptanol Production Process


- Similarities with Pentanal process
- Hydroformylation of C4 alkenes and hydrogenation
- Requirement for compressor unit during stabilization








Real Plant Startup Experience: Pentanal vs. 2-Propylheptanol



Real Plant Startup Experience: Pentanal vs. 2-Propylheptanol



Comparison of startup experiences

- Benefits of virtual commissioning evident in Pentanal process
- Pentanal process: 2 successful startups in 1.6 days, running for 17.0 days
- 2-Propylheptanol process: Extended startup period of 11.4 days with 7 attempts, running for 10.4 days



Conslusions

Virtual commissioning as a valuable tool for process optimization and ICSS verification

Comprehensive verification of ICSS Logics

Verify the Commissioning Procedure

Shorten first start-up

Minimize incidents

Reduce unplanned shutdowns

Minimize flaring and emission through improvement of process operations

Improve plant Reliability & Safety



